




Confined Disposal Facilities (CDFs) within Portland Harbor

Presentation to Community Advisory Group
October 10, 2012

Sean Sheldrake, USEPA Region 10

Chip Humphrey, USEPA Region 10

Possible CDF Locations



Source: LWG

CDF Overview



- CDFs used to manage sediments from navigation and environmental dredging projects nationwide
- CDFs are one option being considered at Portland Harbor to manage contaminated sediments
- CDFs may be a cost effective and protective approach for management of some contaminated sediments at Portland Harbor
- CDF design will consider the need for environmental controls
- Site data will be used to determine suitability of material for placement within any Portland Harbor CDF
- Performance standards for long-term environmental protection must be established
- Monitoring will be performed to ensure protectiveness

CDFs – Some Pros and Cons



- Negative Effects
 - Loss of bottom habitat
 - Potential for releases during filling if not properly conducted
 - Potential for long-term release of contaminants
- Positive Effects
 - Cost effective long-term sediment management
 - Facilitation of dredging projects
 - Potential for the creation of new land for redevelopment and recreation
 - Potential for the creation of shallow water, wetland, and riparian habitat through mitigation

Arkema CDF



- Arkema CDF included as a removal action alternative in Draft Engineering Evaluation and Cost Analysis (EE/CA)
 - Arkema CDF evaluation allowed after 2008 dispute decision and is retained as Alternative 5 in the EE/CA document. A Removal Action Area (RAA) consisting of the area exceeding 5 parts per million DDT (and its breakdown products) was identified for EE/CA evaluation
 - The EE/CA will be used as the basis for selecting a cleanup action within the Removal Action Area boundary at the Arkema site
 - The EE/CA was submitted to EPA on July 26, 2012 and is currently under review by the government team in conjunction with the Gasco EE/CA and Portland Harbor Feasibility Study (FS)
 - Conceptual alternatives evaluated in the EE/CA include removal with capping, removal with backfilling, and removal with backfilling and a nearshore CDF; monitored natural recovery (MNR) and/or enhanced natural recovery (ENR) is proposed for areas with lower level contamination

Arkema CDF




- EE/CA Alternative 5 calls for constructing a CDF around a portion of the contaminated sediment
 - The CDF concept consists of a sheetpile wall keyed into the upland groundwater source control barrier wall
 - Areas outside of the CDF exceeding DDT (and breakdown products) action levels will be dredged to a maximum depth of 15 feet and backfilled to grade
 - An estimated volume of 57,000 cubic yards of dredged material would be placed in the CDF
 - Only material from the Arkema site would be placed in the CDF
 - Sediment contamination within the Removal Action Area below DDT (and breakdown products) action levels would be addressed through MNR/ENR
 - The CDF will include a cover suitable for industrial use and construction of a new vessel berthing area

Arkema CDF



Dredge with onsite CDF Disposal

Potential future berthing area



CDF Sheetpile Cut Off

Nearshore CDF with industrial use cover

Arkema CDF




- EPA's Expectations for Arkema CDF Evaluation
 - Floodway Impacts Analysis – evaluate if CDF will cause unacceptable flood rise and flood storage impacts
 - Short-Term Contaminant Transport – evaluate use of rigid containment for dredging outside of CDF to minimize releases
 - Habitat Impacts and Mitigation – evaluate mitigation needed due to potential habitat loss (fisheries and wildlife impacts)
 - Geotechnical considerations – need to demonstrate barrier wall is sufficiently “keyed” into the underlying bedrock
 - Hydraulic Containment – evaluate the potential for contaminants to migrate out of the CDF via groundwater
 - Evaluate and comply with harbor-wide performance standards (standards to be discussed in later slides)
 - Treatment Technologies – need to identify a list of both in-situ and ex-situ technologies that can enhance the performance of the CDF such as solidification and thermal desorption

Terminal 4 CDF



- 2003: EPA and Port of Portland entered into Administrative Order on Consent (AOC) for performance of non-time critical removal action at Terminal 4
- 2005: The Port of Portland submitted an EE/CA to EPA
- 2006: EPA Action Memo selected a remedy that includes monitored natural recovery (MNR), capping, dredging and placement of contaminated sediment in a CDF to be built in Slip 1
- 2006: 30% Remedial Design submitted
- 2007: Revised schedule and abatement measures approved by EPA
- 2011: 60% Remedial Design submitted


T4 CDF Conceptual Layout




T4 CDF Design Elements and Schedule



- CDF Design Elements
 - Construct a permeable containment berm at the head of Slip 1
 - Place contaminated sediments from Portland Harbor site in Slip 1
 - Construct a CDF cover
- Schedule
 - Portland Harbor FS evaluates disposal of contaminated sediments in the T4 CDF
 - Portland Harbor ROD will specify material to be disposed in CDF
 - Construction will begin following ROD
 - Construction timeframe of 7 to 10 years depending on Portland Harbor cleanup schedule




T4 CDF Design Plan



NOTE:

CONTRACTOR CAN USE TRAINING TERRACES TO BUILD THE BERM. THE TERRACES SHALL EACH BE 20' IN HEIGHT. SEE SPECIFICATIONS FOR MORE DETAILS.





Swan Island Lagoon CDF



- Portland Harbor FS Identified Swan Island Lagoon as potential sediment disposal site (CDF and Confined Aquatic Disposal [CAD])
- Swan Island Lagoon CAD Option
 - Below water (creation of shallow water habitat)
 - CAD cell constructed by building a submerged berm
 - Most promising CAD option identified in Portland Harbor FS
- Swan Island Lagoon CDF Option
 - Above water (creation of developable land)
 - Swan Island Lagoon CDF design similar to T4 CDF
 - Contained on three sides by existing shoreline
 - Isolated from the Willamette River by containment berm
 - Swan Island CDF must comply with T4 performance standards
- Both options require cooperation of nearby landowners
- The ROD is the administrative document in which EPA will identify if the Swan Island Lagoon CDF or CAD has been selected

Swan Island Lagoon CAD



LEGEND:



Cross Section Location



Area of Disposal

CAD - Confined Aquatic Disposal

HORIZONTAL DATUM: Oregon State Plane North, NAD83 (International Feet).
VERTICAL DATUM: North American Vertical Datum of 1988 (NAVD88).

NOTES:



1. Bathymetry from the LWG database. Some assumptions made on the upland topography above the LWG project elevation of +13' NAVD88. These data will need to be confirmed during subsequent design.



DO NOT QUOTE OR CITE
This document is currently under review by US EPA
and its federal, state, and tribal partners, and is
subject to change in whole or in part

Figure 7
Portland Harbor RI/FS
Draft Feasibility Study
Swan Island Lagoon CAD

Swan Island Lagoon CDF



Section A-A'
Scale: 1 = 400' (H)
Vert. Exaggeration: 5X

LEGEND:

- Cross Section Location
- Area of Disposal
- CDF - Confined Disposal Facility

HORIZONTAL DATUM: Oregon State Plane North, NAD83 (International Feet).
VERTICAL DATUM: North American Vertical Datum of 1988 (NAVD88).

NOTES:

1. Bathymetry from the LWG database. Some assumptions made on the upland topography above the LWG project elevation of +13' NAVD88. These data will need to be confirmed during subsequent design.



DO NOT QUOTE OR CITE
This document is currently under review by US EPA and its federal, state, and tribal partners, and is subject to change in whole or in part

Figure 8
Portland Harbor RI/FS
Draft Feasibility Study
Swan Island Lagoon CDF

Portland Harbor Contaminants



- Primary contaminants of concern in Portland Harbor consist of PCBs, dioxin/furans, pesticide DDT, and polycyclic aromatic hydrocarbons (PAHs)
- Volatile chemicals and nuisance odors can be present at dredging and CDF filling operations
- The primary contaminants in Portland Harbor are generally non-volatile
- Sediments from dredge sites containing high concentrations of volatile chemicals are likely not suitable for placement in CDFs without undergoing treatment to meet CDF acceptance criteria
- Monitoring for volatilization and nuisance odors during CDF filling may occur if needed
- Best management practices (BMPs) such as controlling the rate and manner of filling can be implemented to limit volatilization and nuisance odors

Disposal Site Selection Process



- Portland Harbor FS is evaluating a range of disposal options
 - CDFs (Arkema, T4, and Swan Island Lagoon)
 - CADs (Ross Island, Columbia River, and Swan Island Lagoon)
 - Upland disposal (five upland landfills)
- The Portland Harbor ROD will identify which sediment may be disposed of where
 - Consider contaminant concentration and leachability
 - Consider hazardous waste characteristics
- Details regarding construction of on-site CDFs and CADs will be developed during remedial design
- On-site CDFs and CADs must comply with applicable performance standards

FS Alternatives Evaluation

9 Criteria



Superfund requires each cleanup alternative undergo an evaluation on the basis of nine criteria. The objective is to compare and contrast the alternatives so that decision makers may select a preferred alternative.

- **Threshold Criteria** – must be met for an alternative to be considered
 1. Overall protection of human health and the environment
 2. Compliance with applicable relevant and appropriate requirements (ARARs)

FS Alternatives Evaluation

9 Criteria



- **Balancing Criteria** – Once an alternative has passed the first threshold it is balanced against the others that also passed using the following balancing criteria:
 3. Long-term effectiveness
 4. Reduction of mobility, toxicity, and volume through treatment
 5. Short-term effectiveness
 6. Implementability
 7. Cost

FS Alternatives Evaluation

9 Criteria



- **Modifying Criteria** – After balancing the alternatives against each other an alternative that best satisfies each of the balancing criteria is considered for proposed selection based upon the following:
 8. State acceptance
 9. Community acceptance

CDF Performance Standards



- Contain the volume, level, and characteristics of contaminated sediment
- Minimize physical intrusion into waters of the United States
- Minimize water flow into and out of the CDF
- Confine hazardous substances such that the CDF does not contribute any long-term discharge and/or release of contaminants above water quality criteria
- Limit contaminant concentrations in groundwater (including berm pore water) exiting the CDF to levels below EPA's national recommended chronic water quality criteria

CDF Performance Standards



- Design the CDF in a manner that is consistent with the Remedial Action Objectives and Management Goals for the Portland Harbor site
- Design CDF berms to:
 - Provide a static safety factor of 1.5 or greater and a seismic safety factor of 1.1 or greater
 - Be resistant to erosive forces by the largest of 100-year flood flow, 100-year waves, vessel-induced waves and prop wash from typical passing vessels
 - Have an appropriate gradation to allow transport of groundwater while retaining (filtering) sediment during filling and after closure
- Ensure that the CDF will not measurably increase the 100-year flooding stage or decrease flood storage of the Willamette River.

CDF Performance Standards



- Maintain saturated or unsaturated conditions (as appropriate) within the confined contaminated sediments
- Minimize releases of 303(d) listed contaminants to the extent practicable
- Meet all performance standards, Applicable or Relevant and Appropriate Requirements (ARARs), and the final Portland Harbor ROD requirements in perpetuity
- Minimize, to the extent practicable, water quality exceedances within the construction zone and achieve compliance with water quality criteria/standards at and beyond the specified point of compliance

CDF Performance Standards



- Minimize impacts to fisheries and wildlife by removing fish to the extent practicable from the CDF area before and during berm construction
- The CDF berm will be constructed from clean granular material free of roots, inappropriate organic material, contaminants, and all other deleterious and objectionable material
- Accept only sediments meeting final sediment acceptance criteria subject to EPA approval
- Avoid or minimize short-term overflows
- During filling of the CDF, groundwater (berm pore water) exiting the CDF must meet acute water quality criteria

CDF Performance Standards



- Physically close any hydraulic connection between river and the CDF (except through groundwater) during construction except during periods of actual approved overflow
- Manage the CDF in a manner that minimizes impacts to fisheries and wildlife
- Cap contaminated sediments with acceptable clean soils/sediment
- Stormwater discharges or infiltration of stormwater into the CDF is not allowed
- Monitor CDF(s) in perpetuity, or until reduced monitoring is approved by EPA

CDF Performance Standards



- Provide appropriate financial assurance for project development, closure, long-term monitoring, mitigation as needed, and contingency actions
- Implement appropriate institutional controls to:
 - Prevent disturbance of the sediment
 - Prevent stormwater infiltration into the CDF or the CDF buffer zone
 - Prevent installation of groundwater extraction wells for any purpose within the CDF or the CDF buffer zone
 - Restrict development on the CDF

CDF Remedial Design Considerations



- Berm and cap construction and materials
- Liner materials and placement
- Filling sequence and methodology
- Environmental controls during filling
- Seismic stability and resistance to large scale floods
- Vessel induced waves and prop wash
- Long-term monitoring requirements
- Stormwater management
- Habitat mitigation
- Institutional controls

Community Involvement and Remedy Selection



- National Contingency Plan (NCP) identifies community acceptance as a modifying criteria
- Involving the community early and often is one of the 11 principles for managing contaminated sediment sites
- Viable disposal options will be identified in the Proposed Plan which will be issued for public review and comment
- Additional input from EPA?

EPA Contact



Sean Sheldrake – (206) 553-1220

Chip Humphrey – (503) 326-2678

- Additional Information

<http://www.epa.gov/region10/portlandharbor>